

March 24, 2022

ADDENDUM NO. 2



RE: Building 2000 Interior Modifications
WV Regional Technology Park
Bridge Valley Community and Technical College
2001 Union Carbide Drive
South Charleston, WV
Architect's Project No. 22008

TO: Prospective Bidders

FROM: ZMM, Inc. Architects and Engineers

This Addendum forms a part of the Contract Documents and modifies the original Bidding Documents.

ATTACH THIS ADDENDUM TO THE FRONT COVER OF THE PROJECT MANUAL AND ACKNOWLEDGE RECEIPT OF THIS ADDENDUM IN THE SPACE PROVIDED ON THE BID FORM.

PART 1 - CHANGES TO SPECIFICATIONS

- A. Section 102600 "Wall and Door Protection" – Note the following revisions:
1. ADD Inpro Corporation as additional manufacturer for products specified in this Section.
 2. ADD Article 2.4 to read: ABUSE-RESISTANT WALL COVERINGS
 - a. Abuse-Resistant Sheet Wall Covering WP-1: Fabricated from semirigid, plastic sheet wall-covering material.
 - b. Manufacturers: Subject to compliance with requirements, provide Inpro Palladium Rigid Sheet protection panels or comparable products by one of the following:
 1. Construction Specialties, Inc.
 2. Koroseal Interior Products, LLC.
 3. Nystrom, Inc.
 4. Pawling Corporation.
 - c. Size: As indicated.
 - d. Sheet Thickness: 1.5 mm.
 - e. Color and Texture: As indicated on Drawings.
 - f. Height: As indicated on Drawings.
 - g. Trim and Joint Moldings: Extruded rigid plastic that matches wall-covering color.
 - h. Mounting: Adhesive.

Blacksburg
200 Country Club Drive SW
Plaza One, Building E
Blacksburg, Virginia 24060
540•552•2151

Charleston
222 Lee Street West
Charleston, West Virginia 25302
304•342•0159
www.zmm.com

Martinsburg
5550 Winchester Avenue
Berkeley Business Park, Suite 5
Martinsburg, West Virginia 25405
304•342•0159

- B. Section 105113.13 “HDPE Lockers” – Clarification: ADD Line 2.3.A.2 to read: “Lockers by additional manufacturers are to match configuration of Basis of Design Lockers.”

PART 2 - CHANGES TO DRAWINGS

- A. Sheet A131 Floor Plans - Detail 2/A131: Add the following General Note No. 5 to read as follows:
1. Bottom of existing steel floor deck above is +/- 11 feet 8 inches above finished floor.
 2. Existing ceiling in this areas is +/- 9 feet 0 inches above finished floor.
 3. New gypsum wall board bulkhead is to be 8 feet 10 inches above finished floor.

END OF ADDENDUM

Blacksburg
200 Country Club Drive SW
Plaza One, Building E
Blacksburg, Virginia 24060
540•552•2151

Charleston
222 Lee Street West
Charleston, West Virginia 25302
304•342•0159
www.zmm.com

Martinsburg
5550 Winchester Avenue
Berkeley Business Park, Suite 5
Martinsburg, West Virginia 25405
304•342•0159