# August 2, 2022

# **ADDENDUM NO. 4**

RE: Stair Renovations for Davis Hall Bridge Valley Community and Technical College West Virginia Council for Community and Technical College Education Montgomery, West Virginia Architect's Project No. 21168



TO: Prospective Bidders

### FROM: ZMM, Inc. Architects and Engineers

This Addendum forms a part of the Contract Documents and modifies the original Bidding Documents.

# ATTACH THIS ADDENDUM TO THE FRONT COVER OF THE PROJECT MANUAL AND ACKNOWLEDGE RECEIPT OF THIS ADDENDUM IN THE SPACE PROVIDED ON THE BID FORM.

#### PART 1 - INFORMATION FOR BIDDERS

- A. Bid Due Date is postponed until 3:00 p.m. Thursday, August 18, 2022.
- B. Attached is a copy of the report from the testing agency that performed testing for the presence of lead paint on the steel stairs. Lead is present and the Contractor shall follow OSHA guidelines for exposure assessment and provide interim protection as described in the attached report from Pinnacle Consultants.
- C. Refer to Hazardous Materials Report Release Form as attached to this Addendum. Complete this form and return to ZMM Architects Engineers.

### END OF ADDENDUM

Attachments:	Lead Testing Report	6 pages
	Hazardous Materials Report Release Form	

Blacksburg 200 Country Club Drive SW Plaza One, Building E Blacksburg, Virginia 24060 540•552•2151 Charleston 222 Lee Street West Charleston, West Virginia 25302 304•342•0159 www.zmm.com Martinsburg 5550 Winchester Avenue Berkeley Business Park, Suite 5 Martinsburg, West Virginia 25405 304•342•0159

Page 1 of 1



July 18, 2022

Mr. Donald Morris Astar Abatement 539 Kanawha Two Mile Road Charleston, WV 25312

Re: Limited Lead testing for Stairwells at Davis Hall in Montgomery, WV Pinnacle PN: 22-511

Dear Mr. Morris:

On July 8, 2022, Mr. Michael Pauley of Pinnacle Consultants, LLC. visited the above referenced project for the purpose of identifying lead-based paint on the specified incinerator. OSHA defines lead containing material as any material that has a measurable amount of lead present. The owner may at their own liability assume instrument readings of 0.0 mg/cm<sup>2</sup> to be non-lead containing, however, Pinnacle recommends confirming with a paint chip sample.

For this report the following levels were applied to the results in order to comply with all regulations:

Any level 1.0 mg/cm<sup>2</sup> or above is considered to be "Lead-Based Paint" Any level between 0.0 and 1.0 mg/cm<sup>2</sup> is considered to be "Lead Containing Paint" Any level 0.0 mg/cm<sup>2</sup> or below is "Presumed to be Lead Containing Paint"

Based upon the results of the sample analysis for lead content, the OSHA lead standard for construction (29 CFR 1926.62) would apply where any employee may be occupationally exposed to lead. This includes demolition of structures where lead-containing materials are present, removal, new construction, alteration, or renovation of structures or substrates that contain lead. OSHA does not define lead-containing paint or materials or specify a minimum lead content for materials that fall under 29 CFR 1926.62. Essentially, work with any lead-containing material that will be disturbed during construction activity has the potential to cause occupational exposure to lead. The applicability of specific sections of the standard and the need to comply with specific requirements depends on the actual exposure employees experience when performing construction activities in or outside buildings or equipment where lead-containing materials are present.

Accordingly, OSHA requires that each employer performing operations covered by the standard conduct exposure assessments to determine if their employees are exposed to lead above the action level or the

www.pinnaclecorp.net Page 1 of 2 Tel: 304-757-5204 Fax: 304-757-5205



permissible exposure limit (PEL). Worker exposures above the action level or PEL trigger specific actions the employer must take to control and limit exposures to lead.

Until the employer performs an exposure assessment and determines actual employee exposures, the employer is required by the standard to provide employees performing construction work with interim protection as described below.

- Appropriate respiratory protection in accordance with paragraph (f) of the standard.
- Appropriate personal protective clothing and equipment in accordance with paragraph(g).
- Change areas in accordance with paragraph (i)(2).
- Hand washing facilities in accordance with paragraph (i)(5).
- Biological monitoring in accordance with paragraph (j)(1)(i), to consist of blood sampling and analysis for lead and zinc protoporphyrin levels.
  - Training as required under paragraph (l)(2)(ii)(C) concerning hazards associated with exposure to lead.

If future renovations disturb component surfaces that were not sampled during this survey, the renovation process should be halted, and those surfaces should be sampled for lead based paint.

According to OSHA, these interim protection requirements apply to any employee engaged in any construction activity with potential for lead exposure until the employer performs an employee exposure assessment and documents that the employee's lead exposure is not above the action level or PEL

Pinnacle greatly appreciates the opportunity to offer our services to you for this most important project. Should you have any questions or require additional information, please feel free to contact me at your earliest convenience (304) 757-5204.

Sincerely, Pinnacle Consultants, LLC *Michael G. Pauley* 

Michael G. Pauley

500B Prestige Park Drive Hurricane, West Virginia 25526 www.pinnaclecorp.net Page 2 of 2 Tel: 304-757-5204 Fax: 304-757-5205 CompanyViken DetectionModelPb200iTypeXRF Lead Paint AnalyzerSerial Num2395App VersicPb200i-5.2.0

Job Id	Reading # or	ncentratic	Units	Result	pration Rea	ction Leve	Date	Time	Job	Room	RoomChoi	Structure	>Member	Substrate	Wall	Location	Condition	>Cause
7080947	1	0.9	mg/cm2		TRUE	1	7/8/2022	9:47:59	22-511									
7080947	2	1	mg/cm2		TRUE	1	7/8/2022	9:48:11	22-511									
7080947	3	0.9	mg/cm2		TRUE	1	7/8/2022	9:48:22	22-511									
7080947	4	0	mg/cm2		TRUE	1	7/8/2022	9:48:39	22-511									
7080947	5	0	mg/cm2		TRUE	1	7/8/2022	9:48:45	22-511									
7080947	6	0	mg/cm2		TRUE	1	7/8/2022	9:48:52	22-511									
7080947	7	0.5	mg/cm2	Positive	FALSE	0.1	7/8/2022	9:51:12	22-511	Common	Stairwell	Stair	Stringer	Metal	D	8	Intact	
7080947	8	0.1	mg/cm2	Positive	FALSE	0.1	7/8/2022	9:51:32	22-511	Common	Stairwell	Stair	Balusters	Metal	D	8	Intact	
7080947	9	0.1	mg/cm2	Positive	FALSE	0.1	7/8/2022	9:51:44	22-511	Common	Stairwell	Stair	Balusters	Metal	D	8	Intact	
7080947	10	0.2	mg/cm2	Positive	FALSE	0.1	7/8/2022	9:52:22	22-511	Common	Stairwell	Stair	Railing	Metal	D	8	Intact	
7080947	11	0.1	mg/cm2	Positive	FALSE	0.1	7/8/2022	9:52:55	22-511	Common	Stairwell	Stair	Treads	Metal	D	8	Intact	
7080947	12	0.2	mg/cm2	Positive	FALSE	0.1	7/8/2022	9:54:41	22-511	Common	Stairwell	Stair	Treads	Metal	В	2	Intact	
7080947	13	0.1	mg/cm2	Positive	FALSE	0.1	7/8/2022	9:55:05	22-511	Common	Stairwell	Stair	Stringer	Metal	В	2	Intact	
7080947	14	0.1	mg/cm2	Positive	FALSE	0.1	7/8/2022	9:55:31	22-511	Common	Stairwell	Stair	Balusters	Metal	В	2	Intact	
7080947	15	0.1	mg/cm2	Positive	FALSE	0.1	7/8/2022	9:55:49	22-511	Common	Stairwell	Stair	Railing	Metal	В	2	Intact	
7080947	16	0.2	mg/cm2	Positive	FALSE	0.1	7/8/2022	9:56:06	22-511	Common	Stairwell	Stair	Underside	Metal	В	2	Intact	
7080947	17	0.9	mg/cm2		TRUE	1	7/8/2022	9:58:43	22-511									
7080947	18	1	mg/cm2		TRUE	1	7/8/2022	9:58:56	22-511									
7080947	19	1	mg/cm2		TRUE	1	7/8/2022	9:59:27	22-511									
7080947	20	0	mg/cm2		TRUE	1	7/8/2022	9:59:47	22-511									
7080947	21	0	mg/cm2		TRUE	1	7/8/2022	9:59:57	22-511									
7080947	22	0	mg/cm2		TRUE	1	7/8/2022	10:00:04	22-511									

# **WEST VIRGINIA**

Lead Program

Michael G. Pauley

IS LICENSED AS AN LEAD INSPECTOR

> Director WV OEHS



Student Address: 214 Junebug Way, Elkview, WV 25071

Has attended and satisfactorily passed an examination covering the contents of an approved course titled Lead Inspector Refresher (8-Hour)

7322040013 Certificate Number

232-41-3024 Social Security Number

> April 19, 2022 Course Date

April 19, 2022 Exam Date

April 19, 2025 **Expiration Date** 



4186 Innslake Drive Glen Allen, Virginia 23060 (804) 320-9300

EPA Approved Under Title X

Roanoke, VA Location

P1000690

2/9/2022

2/28/2023

Alielp C film

Phillip Fincher, Training Program Manager

Chadwick Bowman, Primary Instructor

3331001412 Course Approval Number

# WEST VIRGINIA

Lead Program

Michael G. Pauley

IS LICENSED AS AN LEAD RISK ASSESSOR

> Director WV OEHS



"anian Studi	Lines .
License #:	PA000419
Issued:	2/9/2022
Expires:	2/28/2023
Muchalle	L. Cocl

Student Address: 214 Junebug Way, Elkview, WV 25071
Has attended and satisfactorily passed an examination
covering the contents of an approved course titled

Lead Risk Assessor Refresher (8-Hour)

7322040015 Certificate Number

232-41-3024 Social Security Number

> April 20, 2022 Course Date

April 20, 2022 Exam Date

April 20, 2025 Expiration Date



4186 Innslake Drive Glen Allen, Virginia 23060 (804) 320-9300

EPA Approved Under Title X Roanoke, VA Location

Alielp C film

Phillip Fincher, Training Program Manager

his lunte

Eric Cureton, Primary Instructor

3331001570 Course Approval Number

Pertificate of Achievement

This is to certify that

# **Michael Pauley**

# Astar Abatement

on the 20th of February, 2014 successfully completed the factory training for

# Dynasil Products XRF Lead Paint Inspection System

Including, but not limited to, the topics of Radiation Safety, DOT Regulations, Haz-Mat Security Awareness and the Proper Use of the Instrument.

Paul A. Delmonico, Sales Manager, Dynasil Products

44 Hunt Street, Watertown, Massachusetts

### HAZARDOUS MATERIALS REPORT RELEASE FORM

# FOR THE

# STAIR RENOVATIONS FOR DAVIS HALL

# BRIDGE VALLEY COMMUNITY AND TECHNICAL COLLEGE

# MONTGOMERY, WEST VIRGINIA



### 1.1 PROJECT CONDITIONS

- A. Hazardous Materials Information: Data from limited investigation reports are available to the Contractor for information only. Conditions are not intended as representations or warranties of accuracy or continuity between samples analyzed and described. The Owner will not be responsible for interpretations or conclusions drawn from this data by Contractor.
  - 1. Bidders must satisfy themselves by personal examination of the site of the Work and by such other means as they may wish as to the actual conditions there existing. Additional sampling, analysis, and other exploratory operations may be performed by Bidder as coordinated with the Architect and Owner.
  - 2. Data is made available for the convenience of the Contractor. Data may be obtained from the Owner by a legal representative of Bidder completing this form as follows:
    - a. "Please forward copy of Hazardous Materials Investigation Report for Stair Renovations for Davis Hall at Bridge Valley Community/Technical College to:

Date: (Bidder) herein releases the Owner and Architect from any responsibility or obligations as to its accuracy or completeness or for any additional compensation for work performed under the contract due to the assumptions based on use of such furnished information or data."

SIGNATURE OF BIDDER:

b.

Firm:\_\_\_\_\_

Address:

Title:

By:\_\_\_\_

Address:

Phone:\_\_\_\_\_